

The Following is a

# YC Directory Cost Estimation

Area: 450 ft²   Voltage: 240   Total Draw: 16.20 KW

Issued on

May 28, 2025

	Est. Install Time <i>(Crew of 2 people)</i>	Subtotal
<b>Heated Pavement Products</b>		
<b>Heating Cables</b> Supply and install High quality 10 year warranty commercial grade heating cables at 36 w/ft2 to ensure least amount of electrical draw on the building. Label all cables, Test before, during and after installation. Covering at least 95% of total heated area.	H 9.00	\$ 4 279,50
<b>Cable Ties And Anchors</b>		\$ 112,50
<b>Panel</b> Supply main heated pavement contactor panel on 3/4" plywood. Bring all cables into building, and connect them to snowmelting panel. All electrical work done by certified electrician		\$ 3 700,00
<b>Controller</b> Supply and setup integrated sensor-less preheating controller for maximum performance. This controller operates with a preheating monitoring service. The customer will need to enroll in the monitoring package of their choice to activate the functionalities of the controller.		\$ 1 120,00
<b>Preparation Products</b>		
<b>Stabilizing Grid</b> Supply and install 1.75" plastic stabilizing grid to anchor cables and weigh down rigid insulation, and fill with 1/8" angular clean gravel.	H 4.50	\$ 1 800,00
<b>Rigid Insulation</b>	H 6.75	\$ 1 125,00

**Est. Install Time**  
*(Crew of 2 people)*

**Subtotal**

Supply and install 60 PSI rigid insulation to maximize energy efficiency and increase performance.

### Notes to Contractor

- It is the responsibility of the landscape contractor to ensure adequate drainage of their paving surface.
- This price does not include any landscaping preparation work or cable embedment / paving work, that cost is to be added above and beyond this quote.
- Any time the total requested power is more than half of the building's capacity, It is highly recommended to have the project evaluated by a qualified electrician prior to engaging in the project.
- This price does not include supplying the contactor panel with power, this will be estimated after an electrician's onsite visit.
- The labour time is displayed as a time per 2 person crew

---

Total	H 20.25	\$ 12 137,00
-------	---------	--------------

**Total Price After Heethr Member Discount: \$ 11 676,40**

***Total savings after discount: \$460,60***

*Thank you for being an early member*

*Prices do not include shipping or taxes*